
ADDENDUM 1

To Whom it May Concern

Re: RFQ 2017-03
Palmerston Arena Dressing Room Floor Replacement 2017

May 10, 2017

In connection with the above noted project, the following addition has been made (in red):

15.0 SCHEDULE A

- a) Supply 3000 square feet of rubber tile flooring. The rubber tile shall be a minimum of 10mm thick and have a minimum 2mm thickness in the top coloured layer. Supply enough 2 part polyurethane adhesive to have the tile glued to the floor.
- b) Install 3000 square feet of rubber tile flooring as directed ensuring proper preparation on existing floor is completed prior to installation.
- c) Variations on overall thickness of the tile may be considered for up to 10%

Please replace your page 10 with the attached amended page.

If you have any further questions, please contact the undersigned:

Yours Truly

Al Carr
Facilities Manager, Town of Minto
519-323-7039
al@town.minto.on.ca

12.0 WITHDRAWAL

The Town reserves the right to withdraw, at its discretion, this Request for Quotation at any time and shall not be liable for any expense, cost, loss or damage incurred or suffered by any bidder as a result of such withdrawal.

13.0 INDEMNITY

The successful bidder shall indemnify and hold the Town harmless from and against any liability, loss, claims, demands, costs and expenses, including reasonable legal fees occasioned wholly or in part by any acts or omissions either in negligence or nuisance whether willful or otherwise by the successful bidder, its agents, officers, employees or other persons for whom the successful bidder is legally responsible.

14.0 SITE EXAMINATION

Bidders shall carefully examine the Place of Work.

15.0 SCHEDULE A

- a) Supply 3000 square feet of rubber tile flooring. The rubber tile shall be a minimum of 10mm thick and have a minimum 2mm thickness in the top coloured layer. Supply enough 2 part polyurethane adhesive to have the tile glued to the floor.
- b) Install 3000 square feet of rubber tile flooring as directed ensuring proper preparation on existing floor is completed prior to installation.
- c) Variations on overall thickness of the tile may be considered for up to 10%

16.0 CONTRACTOR CONTACT INFORMATION

CONTRACTOR: _____

ADDRESS: _____

HST #: _____

DATE: _____

SIGNATURE: _____

NAME & TITLE: _____