



ADDENDUM 1

To Whom it May Concern

Re: Tender 2015-11
Asphalt

In connection with the above noted project, the following changes have been (in red):

21.0 ASPHALT SPECIFICATIONS

HL 3 (5.4% AC 45% 12.5mm Stone) All work shall be done in accordance with OPSS 310.

6th Line of Minto – supply and place approximately 1,380 Metric Ton of HL2 Modified Sand Padding and supply and place approximately 1,853 Metric Ton of **HL3** Surface to approximately 3250m X 7m X **35mm** compressed thickness (Approximately 22,750 square meters)

Howick-Minto Townline – supply and place approximately 750 Metric Ton of HL2 Modified Sand Padding and supply and place approximately 2650 Metric Ton of **HL3** Surface to approximately 3,400m X 7m X **35mm** compressed thickness (Approximately 23,800 square meters).

(page 14)

26.0 SCHEDULE "A"

New asphalt surface work to be completed on the 6th Line of Minto North of County Road 109 extending 3.25km and also on the Howick-Minto Townline, North of the 13th Line of Minto extending approximately 3.4km to the Clifford Town Limits.

TENDER # 2015 - 11 ASPHALT

NEW ASPHALT SURFACE WORK						
ITEM	DESCRIPTION	QUANTITY	TOTAL TONNE	UNIT PRICE PER TONNE (EXCLUDING HST)	TOTAL (EXCLUDING HST)	
A1	HL-2 Mod. Sand Pad		1,380t			
A2	HL-3	22,750sq/m	1,853t			
A3	HL-2 Mod Sand Pad		750t			
A4	HL-3	23,800sq/m	2,650t			
TOTAL SECTION "A1" THROUGH "A4"					\$	

(page 15)

Please replace your pages 14 and 15 with the attached amended pages.

If you have any further questions, please contact the undersigned:

Yours Truly

Mike McIsaac
Road Foreman Town of Minto
519-338-2511 ext 234
mike@town.minto.on.ca

21.0 ASPHALT SPECIFICATIONS

HL 3 (5.4% AC 45% 12.5mm Stone) All work shall be done in accordance with OPSS 310.

6th Line of Minto – supply and place approximately 1,380 Metric Ton of HL2 Modified Sand Padding and supply and place approximately 1,853 Metric Ton of HL3 Surface to approximately 3250m X 7m X 35mm compressed thickness (Approximately 22,750 square meters)

Howick-Minto Townline – supply and place approximately 750 Metric Ton of HL2 Modified Sand Padding and supply and place approximately 2650 Metric Ton of HL3 Surface to approximately 3,400m X 7m X 35mm compressed thickness (Approximately 23,800 square meters).

22.0 EXISTING DRIVEWAYS

Existing asphalt, concrete or interlocking brick driveways abutting roads proposed for asphalt shall have the edges prepared to create a smooth transition between surfaces. Asphalt placed between the road and driveway shall be the same mix design as specified for that road section. Any milling and/or asphalt required shall be the responsibility of the contractor and shall be included in the Total Tender Price on the Form of Tender.

23.0 ASPHALT JOINTS

All joints and/or terminations abutting existing asphalt surfaces shall be ground to the satisfaction of the Public Works Director prior to commencing asphalt placement. Where required the contractor is responsible for milling around all maintenance holes, catch basins and valves located within the existing asphalt. All milling shall be included in the Total Tendered Price on the Form of Tender. Approximate lineal meters of milling have been provided and are based upon one pass, one and a half (1.5) meters wide.

24.0 ADJUSTMENTS

All required maintenance hole and water valve box adjustments shall be the responsibility of the contractor and shall be included in the Total Tendered Price on the Form of Tender. The Town will accept appropriate sized lift rings for both maintenance hole and water valve boxes to meet the required elevations. Catch Basin adjustments will be completed by the contractor also.

25.0 ASPHALT REPAIRS

Areas of asphalt failure identified to the contractor by the Town of Minto within fourteen (14) days of placement shall be repaired to the satisfaction of the Public

TENDER 2015 - 11

Asphalt

TOWN OF MINTO

Works Director within seven (7) days of such notification. No payment will be made for this asphalt requiring replacement.

26.0 SCHEDULE "A"

New asphalt surface work to be completed on the 6th Line of Minto North of County Road 109 extending 3.25km and also on the Howick-Minto Townline, North of the 13th Line of Minto extending approximately 3.4km to the Clifford Town Limits.

**TENDER # 2015 - 11
ASPHALT**

NEW ASPHALT SURFACE WORK

ITEM	DESCRIPTION	QUANTITY	TOTAL TONNE	UNIT PRICE PER TONNE (EXCLUDING HST)	TOTAL (EXCLUDING HST)	
A1	HL-2 Mod. Sand Pad		1,380t			
A2	HL-3	22,750sq/m	1,853t			
A3	HL-2 Mod Sand Pad		750t			
A4	HL-3	23,800sq/m	2,650t			
TOTAL SECTION "A1" THROUGH "A4"					\$	

CONTRACTOR _____

ADDRESS _____

DATE _____

SIGNATURE _____

NAME & TITLE _____