



## ADDENDUM 1

To Whom it May Concern

Re: RFQ 2015-14  
Remove, Dispose, Replace Sidewalks

---

In connection with the above noted project, the following changes (additions) have been added (in red):

### **6.0 APPLICATION , INSPECTION AND REPAIRS**

-Sidewalk Regular Thickness 5"

-Sidewalk Thickness through residential driveways 6"

-Sidewalk Thickness through Industrial/Commercial Driveways 8"

Minimum base 8" granular A base

Finished sidewalk (s) will require a complete saw cut every 5 feet

Sidewalks will be 5 feet in width

All asphalt used to repair any cuts will be HL-3 at a depth of 60mm.

All topsoil will be screened topsoil at a thickness of 50 mm covered with sufficient amount of turf builder blend approved by the Town of Minto Roads Foreman or Lead Hand.

All end sections of sidewalk require by law indicator lines for the blind.

\*If clarification is needed please ask Town of Minto Roads Foreman or Lead Hand.

Please replace your pages 6 with the attached amended page.

If you have any further questions, please contact the undersigned:

Yours Truly

Mike McIsaac  
Road Foreman Town of Minto  
519-338-2511 ext 234  
[mike@town.minto.on.ca](mailto:mike@town.minto.on.ca)

**RFQ 2015 – 14**  
**REMOVE, DISPOSE, REPLACE SIDEWALK**  
**IN THE TOWN OF MINTO**

---

## **6.0 APPLICATION , INSPECTION AND REPAIRS**

Sidewalk Regular Thickness 5”

Sidewalk Thickness through residential driveways 6”

Sidewalk Thickness through Industrial/Commercial Driveways 8”

Minimum base 8” granular A base

Finished sidewalk (s) will require a complete saw cut every 5 feet

Sidewalks will be 5 feet in width

All asphalt used to repair any cuts will be HL-3 at a depth of 60mm.

All topsoil will be screened topsoil at a thickness of 50 mm covered with sufficient amount of turf builder blend approved by the Town of Minto Roads Forman or Lead Hand.

All end sections of sidewalk require by law indicator lines for the blind.

\*If clarification is needed please ask Town of Minto Roads Forman or Lead Hand.

## **7.0 EQUIPMENT TO BE PROVIDED**

The contractor shall have at their disposal for this work:

-All necessary equipment and tools to fulfil all requirements of this quotation.

-Supply all appropriate signage, equipment and personnel to conform to OTM Book 7.

## **8.0 SUPPLY AND SOURCE OF MATERIAL**

The Town reserves the right to reject any supplier and or materials at the sole discretion of the Town of Minto. The Contractor is to provide all material and source of material as per the terms of this contract.

## **9.0 COMPLETION**

Application of procedure as specified shall commence after June 1, 2015 and must be completed no later than October 31, 2015. Time shall be of the essence in this agreement.

Once the work has commenced, the contractor shall ensure that the work progresses to completion without delays. The only exception to this will be due to weather conditions not being suitable to apply the proper procedure. The Road Foreman will have sole discretion for determining when weather conditions are not suitable for the application.

## **10.0 LIQUIDATED DAMAGES CLAUSE**

It is agreed by the parties to the contract that in case all the work called for under the contract is not finished or completed by October 31, 2015 as set forth in this special